## Model Cosy 11,7 sq. m



Woodcab's are delivered ready to use.

Need an office for two, a dedicated yoga space or a bright workshop?

This model offers the perfect compromise in a space suitable for movement and storage.

Well placed in a garden on the outskirts of town, it combines a comfortable interior with a natural feel.

width: 2.52m Insulation:

dimensions: length: 4.66m roof/ground: 10cm, U = 0.4 W/m2K

Safety: lock with key, double glazing Securit width: 2.14m

Interior length: 4.28m length: 2.20m length:

height: 2.20m ventilation: + adjustable natural air supply net: 9.1m2

Surface:

gross: 11.7m2

• type of heating/cooling
• materials

adjustable feet

Foundations: on stabilized ground /

on stabilized ground /

• green roof and/or solar panels

on stabilized ground /
foundation screw (150cm)

on stabilized ground /

foundation screw (150cm)


on soft ground

Delivery and placement are included in the offer.

Delivery:

#### - THE LAYOUT OF THE MODEL BELOW IS A PROPOSAL -

Woodcab is customizable: you can choose the number and location of glass modules and furniture elements according to your desires.





### BASIC MODEL: COSY\_12 sq. m gross (ext.dim 2,52m/4,66m)

28 250,00 €

| Exterior material: Oiled natural pine cladding  |
|---|
| Walls: 8cm wood fiber insulation (U =0.4 W/m2K)   |
| <b>Roof :</b> EPDM sheet with discharge of water, 10cm wood fiber insulation (U = 0.35 W/ m2K) optional green roof on request, optional solar photovoltaic      |
| Glazed door: double glazing solid wood frames (H205xL90), black metal hardware  |
| <b>Windows:</b> horizontal opening (H90xL205) + large non-opening (H180xL180) double glazing with wooden frame  |
| Ventilation: decentralized silent extractor with heat recovery (Nicoll 320670)  |
| <b>Electricity:</b> connection to the network via waterproof wiring + 2 socket (Niko) 230V black + 1 switch to a light point on the wall, RJ 45 ethernet socket |
| Fire detection: approved smoke detector   |
| Breach security: locks with keys  |
| Interior walls : perforated pine plywood  |
| Ground: raw OSB coating   |
| Foundations: adjustable feet / foundation screws if poor soil _to be validated according to the place   |
| Delivery and installation by crane truck  |
|   |

|    | OPTIONS   |            |
|----|---|------------|
| 14 | External cladding: Supplemental burnt wood cladding Shou Sugi Ban technique       | 750,00 €   |
| 15 | Interior walls: perforated birch plywood  | 880,00 €   |
| 16 | Interior ground material: oak flooring (2,5mm Semi-solid)                         | 1055,00€   |
| 17 | Interior ground material: marmoleum   | 945,00 €   |
| 18 | Partition: Interior partition wall with a door not for the tiny model             | X          |
| 19 | Built-in furniture : desk (360€) + shelf (200€)                                   | 560,00€    |
| 20 | Heating/cooling: hot-cold air conditioner with heat pump without outdoor unit 900 | 1300,00€   |
| 21 | Assembly and delivery: to be validated according to the place                     | 0,00 €     |
| 22 | Extra: green roof   | 920,00€    |
| 23 | Extra: access step  | 250,00 €   |
| 24 | Extra: terrace  | 2 490,00 € |
| 25 | Extra: projection blind   | 1800,00€   |

## Model Cosy 14,4 sq. m



Need an office for two, a dedicated yoga space or a bright workshop?

This model offers the perfect compromise in a space suitable for movement and storage.

Well placed in a garden on the outskirts of town, it combines a comfortable interior with a natural feel.

width: 2.52m Insulation:

net: 11.4m2

dimensions: length: 5.73m roof/ground: 10cm, U = 0.4 W/m2K

**Safety:** lock with key, double glazing Securit

Interior length: 5.35m

dimensions: height: 2.20m

Ventilation: + adjustable natural air supply

Surface:

gross: 14.4m2

• type of heating/cooling
• materials

adjustable feet

Foundations: on stabilized ground /

on stabilized ground /

• green roof and/or solar panels

oundations: on stabilized ground /
foundation screw (150cm)

on stabilized ground /


blinds

on soft ground Delivery and placement are included in the

**Roofing:** EPDM + options **Delivery:** offer. Woodcab's are delivered ready to use.

#### - THE LAYOUT OF THE MODEL BELOW IS A PROPOSAL -

Woodcab is customizable: you can choose the number and location of glass modules and furniture elements according to your desires.






### BASIC MODEL: TINY\_14 sq. m gross (ext.dim 2,52m/5,73m)

33 400,00 €

| Exterior material: Oiled natural pine cladding  |
|---|
| Walls: 8cm wood fiber insulation (U =0.4 W/m2K)   |
| <b>Roof :</b> EPDM sheet with discharge of water, 10cm wood fiber insulation (U = 0.35 W/ m2K) optional green roof on request, optional solar photovoltaic      |
| Glazed door: double glazing solid wood frames (H205xL90), black metal hardware  |
| <b>Windows:</b> horizontal opening (H90xL205) + large non-opening (H180xL180) double glazing with wooden frame  |
| Ventilation: decentralized silent extractor with heat recovery (Nicoll 320670)  |
| <b>Electricity:</b> connection to the network via waterproof wiring + 2 socket (Niko) 230V black + 1 switch to a light point on the wall, RJ 45 ethernet socket |
| Fire detection: approved smoke detector   |
| Breach security: locks with keys  |
| Interior walls : perforated pine plywood  |
| Ground: raw OSB coating   |
| Foundations: adjustable feet / foundation screws if poor soil _to be validated according to the place   |
| Delivery and installation by crane truck  |
|   |

|    | OPTIONS   |           |
|----|---|-----------|
| 14 | External cladding: Supplemental burnt wood cladding Shou Sugi Ban technique       | 875,00 €  |
| 15 | Interior walls: perforated birch plywood  | 1080,00€  |
| 16 | Interior ground material: oak flooring (2,5mm Semi-solid)                         | 1300,00€  |
| 17 | Interior ground material: marmoleum   | 1170,00 € |
| 18 | Partition: Interior partition wall with a door                                    | 1500,00€  |
| 19 | Built-in furniture : desk (360€) + shelf (200€)                                   | 560,00 €  |
| 20 | Heating/cooling: hot-cold air conditioner with heat pump without outdoor unit 900 | 1300,00€  |
| 21 | Assembly and delivery: to be validated according to the place                     | 0,00€     |
| 22 | Extra: green roof   | 1130,00€  |
| 23 | Extra: access step  | 250,00 €  |
| 24 | Extra: terrace  | 2850,00€  |
| 25 | Extra: projection blind   | 1800,00€  |

# 



## Included in your basic Woodcab:

Exterior cladding: Oiled natural pine cladding

Window frames: Larch wood frame, double glazing

**Structure:** KVH spruce wood

**Insulation:** 100% Belgian grass fibre (Gramitherm®)

Sealing:

Roof: black EPDM 1.5mm

Walls and floor: rain screen panels high performance air sealing membrane + tape


Floors: OSB wood panels

Interior wall material: Perforated pine plywood

**Electricity:** 220 volt cable for plug and play connection to the network:

- 2 indoor sockets - 1 switch to a light point - 1 switch to the ventilation

**Ventilation:** Invisible silent motorised extraction + adjustable mechanical air intake



## **Options:**

**Exterior cladding:** Burnt wood covering with the Shou sugi Ban technique

**Interior wall cladding:** Solid or perforated birch or beech plywood

Floor covering: Floating floor in semi-massive oak (2.5mm solid) or Linoleum Forbo Modular

**Partition:** Interior partition wall (not for the model Tiny)

**Built-in furniture:** Shelves size 80 cm or 180 cm, desk, bench

Access step: Massive landing step in burnt wood

**Terrace:** Prefabricated terrace made of local heat-treated wood

Air conditioner with hot/cold heat pump without outdoor unit

• Black design electric radiator

Roof: Green roof

Solar panels on request (redirected to our preferred partner)

Window: Large sliding door (400/200)

Window blind: Projection blinds or straight sliding blinds, electric or manual

## Transport and installation included:

**Foundations:** Removable lightweight foundation screws

**Transport:** Conventional truck (maximum width 252cm)

**Placement:** Via the articulated arm of the truck, mobile crane or other rapid lifting system

EXTRA: crane supplement + distance to be confirmed depending on location

